

Heckaman Homes Modular

Model: Winchester Size: 32' x 62' (floor length) 1860 sq ft.

Base price: \$124,800 (Includes interior finish)

Options:

5/12 pitch Shingle roof/Vinyl siding - Clay	Std	8' flat ceiling T/O	Std
2x10 Floor joists 16" OC	Std	¾" tongue and groove OSB decking	Std
Pex waterlines installed	\$500	2" vent pipe for basement	\$30
3" vent pipe	40	Boots and registers for HVAC	Std
Bullnose corners on TNT	200	8' flat ceilings	Std
2X6 exterior walls (R-21)	Std	Continuous exterior wall vapor barrier	Std
Double switch for ceiling fan/light (4)	140	Add wire prep for garage light	50
Oil rubbed pendant lights - kit bar (3)	90	200 Amp square D 30/40 panel box	Std
Exterior elec outlets (2)	Std	Door chime at front door	Std
Smoke/Carbon Monoxide detectors	Std	6" Flush mount LED light in kit (4)	Std
4" Flush mount LED light over kit sink (1)	Std	110 Gas range & 220 Elec range recep	Std
CertainTeed Landmark arch shingles - Driftwood	Std	16" overhang at sidewalls & 12" on ends	Std
Ice dam prevention	Std	R-40 roof insulation	Std
7/16" OSB sheathing and housewrap	Std	Solid surface counters in both baths	825
Drop in tub and 60" FG shower - Mbath	Std	with undermount sinks - G/502	
Elongated toilets - both baths	Std	Vanity lights with mirrors at all sinks	Std
Upgrade Std. Basic Collins Birch cabs to opt	\$2550	Painted finish w/ accent glaze on cabs	1400
Group A. Upgrade group A to group D - Merrilat		Upgrade Swanstone sink - white	350
Kitchen cabinets - Seneca Ridge Maple Chiffon w/Desert Accent			
Kitchen Island - Seneca Ridge Maple Kona			
Bath cabinets - Seneca Ridge Maple Chiffon w/Desert Accent			
Lazy susan at base corner cabinet	Std	Tip out trays at sink	Std
Switch and wire for garbage disposal	Std	Prep for dishwasher	Std
Laminate counters w/backsplash - Perlato Granite	Std	Bank of drawers - 1 per kitchen area	Std
Staggered wall cabinets	Std	Crown molding on kit cabinets	Std
Raised panel shutters (5 pair)	250	8' Sliding glass door - Anderson	840
Anderson Silverline single hung windows	Std	36" 6 panel fire rated steel door at utility	Std
Upgrade front door with glass - BLS 304-778-3	495	Add window - MBath	200
Pine window jamb IPO std (stained to match)	600	Upgrade std trim to wide width trim	558
Oil rubbed bronze hardwood pkg - includes	1050	32" & 36" interior doors where applicable	Std
Hardware, std light fixtures and plumbing pkg		2 panel white Roman Arch interior doors	Std
Vinyl flooring all wet areas - 9587	Std	New day carpet - 106 Barley	Std

Total options: \$10,168

Home only total: \$134,968

Delivery and Set (within 100 miles): \$9000

Includes: Crane fee, set and anchor home on concrete, simpson straps for anchoring, completion of exterior siding and roof, set jacks for marriage line, installation of dryer vent (not to exceed 15'), carpet completion.